

Tel.No.22875794, 22872801  
Fax 08022374092  
e-mail -  
sebgkpwd@gmail.com



ಕರ್ನಾಟಕ ಸರ್ಕಾರ  
ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರ ಕಚೇರಿ  
ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ  
ಬೆಂಗಳೂರು ವೃತ್ತ, ಬೆಂಗಳೂರು

ಸಂಖ್ಯೆ 4315 / ದಿನಾಂಕ 02-09-2022

### ತಿದ್ದುಪಡಿ -3 : ಸೇರ್ಪಡೆ - 2ರ ಪ್ರಕಟಣೆ

**ವಿಷಯ:** 2021-22ನೇ ಸಾಲಿನ ದರಪಟ್ಟಿಗಳಲ್ಲಿ 3ನೇ ತಿದ್ದುಪಡಿ ಹಾಗೂ 2ನೇ ಸೇರ್ಪಡೆ ಮಾಡುವ ಕುರಿತು.

- ಉಲ್ಲೇಖ:**
- 1) ಸರ್ಕಾರದ ಆದೇಶ ಸಂಖ್ಯೆ : ಲೋಇ 51 ಆರ್.ಡಿ.ಎಫ್ 2019 ದಿನಾಂಕ 18-03-2022
  - 2) ದಿನಾಂಕ : 21-04-2022 ರಲ್ಲಿ ನೀಡಲಾಗಿರುವ ಸೇರ್ಪಡೆ/ತಿದ್ದುಪಡಿ ಪ್ರಕಟಣೆ
  - 3) ದಿನಾಂಕ : 06-07-2022 ರಲ್ಲಿ ನೀಡಲಾಗಿರುವ ತಿದ್ದುಪಡಿ ಪ್ರಕಟಣೆ
  - 4) ದಿನಾಂಕ 03-08-2022 ರಂದು ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು ಹಾಗೂ ಏಕರೂಪ ದರಪಟ್ಟಿಯ ತಯಾರಿಕೆ ಸಮಿತಿಯ ಅಧ್ಯಕ್ಷರು ಇವರ ಅಧ್ಯಕ್ಷತೆಯಲ್ಲಿ ನಡೆದ ಸಭೆಯ ನಡವಳಿಗಳು
  - 5) ಸರ್ಕಾರದ ಪತ್ರ ಸಂಖ್ಯೆ : ಲೋಇ 51 ಆರ್.ಡಿ.ಎಫ್ 2019 ದಿನಾಂಕ 19-08-2022

\*\*\*\*\*

ಸರ್ಕಾರದ ಆದೇಶ ಸಂಖ್ಯೆ : ಲೋಇ 51 ಆರ್.ಡಿ.ಎಫ್ 2019 ದಿನಾಂಕ 18-03-2022 ರಂತೆ ಬಿಡುಗಡೆಯಾಗಿರುವ ಸಂಪುಟ-1, 2 ಮತ್ತು 3 ರ ದರಪಟ್ಟಿಗಳನ್ನು 2022-23 ನೇ ಸಾಲಿಗೆ ಮುಂದುವರಿಸಲಾಗಿರುತ್ತದೆ. ಸದರಿ ದರಪಟ್ಟಿಯ ಸಂಪುಟ-2 ರಲ್ಲಿನ ಸಾಮಾನ್ಯ ಟಿಪ್ಪಣಿ ಸಂಖ್ಯೆ : 30ರಂತೆ ಹಾಗೂ ಸಂಪುಟ-3ರ ಸಾಮಾನ್ಯ ಟಿಪ್ಪಣಿ ಸಂಖ್ಯೆ:17 ರಂತೆ ದರಪಟ್ಟಿಗಳಲ್ಲಿ ಕೆಲವೊಂದು ಹೆಚ್ಚುವರಿ ಅಂಶಗಳ ಸೇರ್ಪಡೆ/ತಿದ್ದುಪಡಿ ಮಾಡಿ ಉಲ್ಲೇಖ (2) ಮತ್ತು (3) ರಂತೆ ಪ್ರಕಟಣೆ ಹೊರಡಿಸಲಾಗಿತ್ತು.

ಮುಂದುವರೆದು, ಕರ್ನಾಟಕ ರಾಜ್ಯ ಗುತ್ತಿಗೆದಾರರ ಸಂಘವು ಸರ್ಕಾರಕ್ಕೆ ಸಲ್ಲಿಸಿರುವ ಮನವಿಗಳಂತೆ ಉಲ್ಲೇಖ (4)ರಲ್ಲಿ ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು ಹಾಗೂ ಏಕರೂಪ ದರಪಟ್ಟಿಯ ತಯಾರಿಕೆ ಸಮಿತಿಯ ಅಧ್ಯಕ್ಷರು ರವರ ಅಧ್ಯಕ್ಷತೆಯಲ್ಲಿನ ಸಭೆಯಲ್ಲಿ ತಾಂತ್ರಿಕ ಕಾರ್ಯನಿರತ ತಂಡ, ಎಲ್ಲಾ ಇಲಾಖೆಗಳ ಹಿರಿಯ ಅಧಿಕಾರಿಗಳು ಮತ್ತು ನುರಿತ ಅಭಿಯಂತರರುಗಳು ನೀಡಿರುವ ತಾಂತ್ರಿಕ ಸಲಹೆಗಳನ್ವಯ ಪ್ರಮುಖವಾಗಿ ಸ್ಪೀಲ್ ಸೆಂಟ್ರಿಂಗ್, ಏರಿಯಾ ಸ್ಪೆಷಿಫಿಕ್ ಲೋಡಿಂಗ್, ಮಣ್ಣಿನ ಕೆಲಸಗಳನ್ನು ಹಾಗೂ ಇನ್ನಿತರೆ ಅಂಶಗಳ ಕುರಿತು ಪರಿಷ್ಕರಣೆಗೊಳಿಸಲು/ ಸೇರ್ಪಡೆಗೊಳಿಸಲು ಚರ್ಚಿಸಲಾಗಿರುತ್ತದೆ. ಅದರಂತೆ, ಸದರಿ ಸಭೆಯಲ್ಲಿನ ನಿರ್ಣಯಗಳಂತೆ ಹಾಗೂ ಸಲಹೆಗಳನ್ನು ಪರಿಗಣಿಸಿ ಉಲ್ಲೇಖ (5) ರಲ್ಲಿ ಸರ್ಕಾರದ ಅನುಮೋದನೆ ಪಡೆದು ಸಂಪುಟ-1ರಲ್ಲಿನ ಪುಟ ಸಂಖ್ಯೆ 115-116 ಮತ್ತು ಎ-54 ರಲ್ಲಿನ ಕೋಷ್ಟಕಗಳನ್ನು ಈ ಕೆಳಕಂಡಂತೆ ತಿದ್ದುಪಡಿ ಮಾಡಲಾಗಿದೆ.



**Corrigendum - 3**

**I : Appendix I - Additionalities for Formwork, Centering & Scaffolding**

REVISION TO 2021-22 VOL.1 COMMON SR - Page : 115-116 W.E.F 01.09.2022

REVISION TO 2021-22 VOL.1 COMMON SR - Page : 115-116 W.E.F 01.09.2022					
As per 2021-22 VOL.1 COMMON SR			REVISED		
Sl No.	Type of structure	Percentage on finished rate of concrete per m <sup>3</sup>	Sl No.	Elements of Structure	Percentage on finished rate of concrete per m <sup>3</sup>
1.	Foundation upto Plinth	-	1.	Foundation upto Plinth	-
	a. Isolated	8%		a. Isolated	8%
	b. All other types	3%		b. All other types	3%
			1a.	<b>Plinth beams of Buildings</b>	<b>50%</b>
2.	Foundation, Sub structure of Cross drainages	5%	2.	Foundation, Sub structure of Cross drainages	5%
			2a.	<b>Cement Concrete Drains</b>	<b>35%</b>
3.	Open Foundation	4%	3.	Open Foundation	4%
4.	Well Foundation	20%	4.	Well Foundation	20%
5.	Road medians, Traffic Separators, Dividers etc	5%	5.	Road medians, Traffic Separators, Dividers etc	5%
6.	Steel Channels for Road works	5%	6.	Steel Channels for Road works	<b>Deleted</b>
7.	Culverts (Head walls)	8%	7.	Culverts (Head walls)	8%
8.	Columns & Piers	10%	8.	<b>Columns</b>	<b>70%</b>
			8a.	<b>Piers &amp; Abutments</b>	10%
9.	Earth retaining structures	10%	9.	Earth retaining structures	10%
10.	Canal lining	10%	10.	Canal lining ( <b>Only Vertical sections</b> )	10%
11.	Dam & Allied works	12%	11.	Dam & Allied works	12%
12.	Beams & Lintels of Building	20%	12.	<b>Beams &amp; lintels of Buildings</b>	<b>60%</b>
13.	Roof (Straight & Arched)	20%	13.	<b>Roof slab of Buildings</b>	<b>50%</b>
14.	Roof (Curved)	22%	14.		
15.	Plastering & Painting of New walls	25%	15.	Plastering & Painting of New walls	<b>Deleted (Corrigendum -1 dated 21-04-2022)</b>
16.	Painting of old walls & ceiling	20%	16.	<b>Painting of Old external walls above floor 2</b>	20%
17.	Plastering & Painting of ceiling	25%	17.	Plastering & Painting of ceiling	<b>Deleted (Corrigendum -1 dated 21-04-2022)</b>



18.	Architectural projection of major sections	30%	18.	Architectural projection of major sections	30%
19.	Domes & Sloped roofs	45%	19.	Domes & Sloped roofs	<b>Deleted</b>
20.	Chejjas, Canopy & Other Architectural projections of minor sections	45%	20.	Chejjas, Canopy & Other Architectural projections of minor sections	45%

### Bridges

1.	Solid Slab Super Structure	20%	1.	Solid Slab Super Structure	20%
2.	T-Beam & Slab	25%	2.	T-Beam & Slab	25%
3.	Box Girder & Balanced Cantilever	38%	3.	Box Girder & Balanced Cantilever	38%
4.	Cast insitu Box girder & Segmental construction	38%	4.	Cast insitu Box girder & Segmental construction	38%
5.	For T-beam & slab, including launching of precast girders by launching truss upto 40 m span	21%	5.	For T-beam & slab, including launching of precast girders by launching truss upto 40 m span	21%
6.	Box Culverts	20%	6.	Box Culverts	20%

### III : Corrections to other Items

SL NO.	VOL.	ITEM NO	PAGE NO.	DESCRIPTION AS PRINTED IN SR (VOL.1, 2 & 3)	CORRECTED AS
1.	2	6.4	13	Providing Brick work with common burnt clay modular bricks of class designation 3.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer incharge of work. <b>The unit is printed as m<sup>2</sup></b>	<b>'m<sup>3</sup>'</b>
2.	2	11.5 5	94	Supplying and fixing turn buckles and straining bolts for barbed wire fencing. <b>The rate is printed as Rs. 1412.00 per set</b>	<b>Rs. 186.00 per set</b>
3.	2	11.5 7.1	94	Fencing with G.I. barbed wire Angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I.staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire <b>The rate is printed as Rs. 52.00 per m</b>	<b>Rs. 15.00 per m</b>



**Addendum - 2**

**I : Area Specific Loading**

REVISION TO 2021-22 VOL.1 COMMON SR - Page : A-54 W.E.F 01.09.2022			
Sl. No	Category	Additional Loading charges	
		As per 2021-22 SR	Revised
1	Tier I city -Bruhat Bangaluru Mahanagara palike Limits (BBMP) (Night work , Traffic diversion, Head load/movement of machinery)	10%	10%
1a.	<b>BDA developed &amp; Notified Areas</b>		<b>7.50%</b>
1b.	<b>BMRDA &amp; Ramanagara District</b>		<b>3%</b>
2	Tier II cities ( Corporation limits of Belagavi, Hubballi-Dharwada, Kalaburgi, Mangaluru, Mysuru, Vijayapura, Davanagere, Shivamogga & Tumkuru )	5%	5%
3	Other Cities, Municipal Limits/Corporation Limits	3%	3%
4	Kalyana Karnataka	5%	5%
5	Restricted areas - Jails/ Forest/ Sewerage works under unhygienic conditions	12%	12%
6	Major Irrigation command area / Mining Area/ Major Industries / Border Area (up to 5 km radius)	5%	5%
7	Coastal Area (upto 25 km from coast), Tidal wave area, Heavy Rain-fall area 1600 mm and above	12%	12%
8	Hilly Terrain above 300 m from the nearest town/city	12%	12%
9	Works in other States	Adopt SR of that State ( City/Circle)	Adopt SR of that State ( City/Circle)

**II : Earthwork Excavation for works costing Rs. 200.00 Crores to Rs. 500.00 Crores**

Sl No.	Item No. (NH SR 2022-23)	Description of Item	Rate in Rs. Per m <sup>3</sup>
1.	3.13 MoRTH 301	Earthwork in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work including all lead, lift, labour, spreading, usage charges of all machineries etc. complete	81.00
2.	3.16 MoRTH 305	Construction of embankment with approved material obtained from borrow pits laid in layers not exceeding 250mm loose thickness, spreading, breaking clods, removal of roots and other organic materials to the required line, grade and cross section including watering, consolidation by roller to the desired field density not less than 95% of maximum dry density including all lead, lifts, loading, unloading, all labour, usage charges of all machinery etc., complete as per table 300-2.	440.00



ಸದರಿ ಪ್ರಕಟಣೆಯನ್ನು ದಿನಾಂಕ 01-09-2022 ರಿಂದ ಅನ್ವಯಿಸುವಂತೆ ಆದೇಶಿಸಲಾಗಿದೆ ಹಾಗೂ ಇಲಾಖೆಯ ಜಾಲತಾಣ [www.kpwd.karnataka.gov.in](http://www.kpwd.karnataka.gov.in) ರಲ್ಲಿ ಪ್ರಕಟಿಸಲಾಗಿದೆ.

-ಸಹಿ-

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು  
ಲೋಇ ಬೆಂಗಳೂರು ವೃತ್ತ

ಪ್ರತಿಯನ್ನು:

1. ಸರ್ಕಾರದ ಅಪರ ಮುಖ್ಯ ಕಾರ್ಯದರ್ಶಿಗಳು, ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ, ವಿಕಾಸ ಸೌಧ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ.
2. ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು, ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ, ವಿಕಾಸ ಸೌಧ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ.
3. ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು, ಜಲಸಂಪನ್ಮೂಲ ಇಲಾಖೆ, ವಿಕಾಸ ಸೌಧ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ.
4. ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು, ಸಣ್ಣ ನೀರಾವರಿ ಇಲಾಖೆ, ವಿಕಾಸ ಸೌಧ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ.
5. ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು, ಪಂಚಾಯತ್ ಇಂಜಿನಿಯರಿಂಗ್ ಇಲಾಖೆ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ.
6. ಪ್ರಧಾನ ಅಭಿಯಂತರರು, ಪ್ರಾಂಸಿ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗೆ ಸಲ್ಲಿಸುತ್ತಾ ಇಲಾಖಾ ವೆಬ್‌ಸೈಟ್‌ನಲ್ಲಿ ಅಪ್‌ಲೋಡ್ ಮಾಡಲು ಕೋರಿದೆ.
7. ಮುಖ್ಯ ಅಭಿಯಂತರರು, ಸಂಪರ್ಕ ಮತ್ತು ಕಟ್ಟಡಗಳು (ದಕ್ಷಿಣ, ಉತ್ತರ, ಈಶಾನ್ಯ ಮತ್ತು ಕೇಂದ್ರ) ರವರುಗಳ ಘನ ಮಾಹಿತಿಗೆ ಸಲ್ಲಿಸಿದೆ.
8. ಮುಖ್ಯ ಅಭಿಯಂತರರು, ಬೆಸ್ಕಾಂ ಕೇಂದ್ರ ಕಚೇರಿ ಬೆಂಗಳೂರು ರವರ ಮಾಹಿತಿಗೆ ಸಲ್ಲಿಸಿದೆ.
9. ಮುಖ್ಯ ಅಭಿಯಂತರರು, ಗ್ರಾಮೀಣಾಭಿವೃದ್ಧಿ ಇಲಾಖೆ, ಬೆಂಗಳೂರು ರವರ ಮಾಹಿತಿಗೆ ಸಲ್ಲಿಸಿದೆ.
10. ನಿರ್ದೇಶಕರು, ಇ-ಪ್ರೊಕ್ಯೂರ್‌ಮೆಂಟ್, ಬಹುಮಹಡಿಗಳ ಕಟ್ಟಡ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗೆ ಸಲ್ಲಿಸುತ್ತಾ, ಇ-ಪ್ರೋಕ್ ಪೋರ್ಟಲ್‌ನಲ್ಲಿ ಸದರಿ ಆದೇಶದಂತೆ ಪರಿಷ್ಕರಣೆಗಳನ್ನು ಅಪ್‌ಲೋಡ್ ಮಾಡಲು ಕೋರಿದೆ.
11. ಮುಖ್ಯ ಅಭಿಯಂತರರು, ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ, ಬೆಂಗಳೂರು ರವರ ಮಾಹಿತಿಗೆ ಸಲ್ಲಿಸಿದೆ.
12. ಮುಖ್ಯ ಅಭಿಯಂತರರು, ಬೆಂಗಳೂರು ಅಭಿವೃದ್ಧಿ ಪ್ರಾಧಿಕಾರ, ಬೆಂಗಳೂರು ರವರ ಮಾಹಿತಿಗೆ ಸಲ್ಲಿಸಿದೆ.
13. ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು, ಲೋಇ ವೃತ್ತ, ಮೈಸೂರು, ಹಾಸನ, ಮಂಗಳೂರು, ಬಳ್ಳಾರಿ, ಕಲ್ಬುರ್ಗಿ, ಬೆಳಗಾವಿ, ಧಾರವಾಡ ಮತ್ತು ಶಿವಮೊಗ್ಗ ರವರುಗಳ ಮಾಹಿತಿಗಾಗಿ ಇ-ಮೇಲ್ ಮುಖಾಂತರ ಕಳುಹಿಸಿದೆ.
14. ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು, ಗ್ರಾಮೀಣಾಭಿವೃದ್ಧಿ ಇಲಾಖೆ, ಬೆಂಗಳೂರು ರವರ ಮಾಹಿತಿಗಾಗಿ ಇ-ಮೇಲ್ ಮುಖಾಂತರ ಕಳುಹಿಸಿದೆ.
15. ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು, ಲೋಇ ವಿಭಾಗ ಬೆಂಗಳೂರು, ರಾಮನಗರ, ರಾಮನಗರ ವಿಶೇಷ, ಕೋಲಾರ, ಚಿಕ್ಕಬಳ್ಳಾಪುರ, ತುಮಕೂರು ಮತ್ತು ಮಧುಗಿರಿ ರವರ ಮಾಹಿತಿಗಾಗಿ ಇ-ಮೇಲ್ ಮುಖಾಂತರ ಕಳುಹಿಸಿದೆ.
16. ಕಚೇರಿ ಪ್ರತಿ

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು  
ಲೋಇ ಬೆಂಗಳೂರು ವೃತ್ತ